

PUBLIC NOTICE OF NETWORK CHANGE UNDER RULE 51.329(a)

February 1, 2022

Subject: Switch Decommission, Switch Power Down

Carrier: Windstream Oklahoma, LLC
4001 North Rodney Parham Road, Little Rock, AR 72212

Notice ID: Network Change Notice SD Oklahoma 001 Version 2

Contact: For additional information on the planned network changes, please contact:

James Seegar
Windstream
1720 Galleria Blvd, Charlotte, NC 28270
704-845-7466 or 704-728-2272
James.Seegar@windstream.com

Change Effective Date: On or after, August 1, 2022

Planned Network Change(s) will occur at the following locations in Oklahoma:

Windstream Central Office	Address	CLLI
Smithville, OK DMS10 Switch	198 Main St, Smithville OK 74957	SMVLOKXADS0
Smithville, OK Meta Switch	198 Main St, Smithville OK 74957	SMVLOKXAPS0
Battiest, OK Remote Switch	10 S Main, Battiest OK 74722	BTSTOKXARS1
Battiest, OK Meta Switch	10 S Main, Battiest OK 74722	BTSTOKXARP0

Website Link to Notice Posting: <https://www.windstream.com/about-windstream/legal/network-change-notifications>

Additional Details:

Description of the Planned Network Change(s):

The DMS switch, located at 198 Main St, Smithville OK 74957, will be decommissioned, powered down, and removed from Windstream’s network as a result of network modernization and consolidation. All traffic will need to be routed to the SMVLOKXAPS0 Meta Switch. Windstream Smithville OK A-Block of 580-244 is being moved to SMVLOKXAPS0. Includes remote Battiest OK A-Block of 580-241

Description of Reasonably Foreseeable Impact(s) of the Planned Change(s):

Competitive local exchange carriers (CLECs), interexchange carriers (IXCs, IECs), wireless carriers, and paging carriers will need to secure new trunk groups built to the SMVLOKXAPS0 Meta Switch or have existing trunk groups to that switch augmented. Carriers that are code

holders for access connectivity in the Smithville OK DMS switch will be required to reposition the codes to the SMVLOKXAPS0 Meta Switch.

All ASRs for the SMVLOKXAPS0 Meta Switch must be received no later than June 1, 2022, in order to provide sufficient time to migrate the traffic described above. These direct end office trunk (DEOT) interconnections will support traffic migration for the Smithville OK DMS switch prior to its eventual decommissioning. Local Exchange Routing Guide (LERG) change effective dates will be posted prior to decommissioning of the Smithville OK DMS switch (on or after June 4, 2022). This will serve to guide interconnect re-routes of Windstream traffic for native codes currently served by the Smithville OK DMS switch to reflect the SMVLOKXAPS0 Meta Switch as the new home switch. All ASRs for the SMVLOKXAPS0 Meta Switch must carry the project code of SMVLOKXAPS0.